

Erosion Control and Grading Notes

1. Erosion control shall be installed on the site for no more than 15 days. Keep dust within tolerable limits by sprinkling or other acceptable means.
2. All cut/fill areas to have a minimum of 6" of topsoil cover. Areas dressed with topsoil shall receive 12 lbs. per 1000 sq. ft. of 10-10-10 fertilizer (unless otherwise specified in written specifications), 5 lbs. or more of Kentucky 31 tesco seed per 1000 sq. ft., and a straw mulch cover of 70%-80% coverage (approximately 125 lbs. per 1000 sq. ft.), unless otherwise noted within written specifications.
3. Erosion control barrier is called out on plans and is to comply with the Metropolitan Stormwater Management Manual, volume four, section TCR-14.
4. Disturbed areas are to be graded to drain as indicated in the plan to sediment barriers during and upon the completion of construction.
5. The contractor shall be responsible for the verification and the location of any existing utilities. It shall be the responsibility of the contractor to avoid damage to all existing utilities during construction. If damage does occur to any such installation, full repair will be accomplished as per the current specification governing such work.
6. Any access routes to the site shall be based with crushed stone, ASTM #1 stone, 100' long and at least 6" thick.
7. The placing and spreading of any fill material is to be started at the lowest point and brought up in horizontal layers of 8" thickness (or as directed by the soils investigative report). Said fill material is to be free of soil, roots, frozen soils, or any other decomposable material. Said fill is to be compacted to a minimum of 95% standard proctor, or as otherwise specified by the soils report or written specifications.
8. The contractor shall notify the Metro Davidson County Department of Public Works construction compliance division, three days prior to beginning the work.
9. The contractor shall locate and stake the layout of the site in the field for inspection by the engineer. The contractor shall check the grades and final dimensions on the ground, and report any discrepancies to the engineer immediately for a drawing.
10. Surplus excavation of topsoil shall be placed on the site as approved by the owner for the purpose of future landscape use.
11. The contractor shall furnish and install all necessary temporary works for the protection of the public and employees, including warning signs and lights.
12. The contractor shall be responsible for any damage done to the premises or adjacent premises or injuries to the public during the construction caused by himself, his sub-contractors, or the carelessness of any of his employees.
13. All work is to be completed with compliance to the rules and regulations set forth by Metro Water Services. The contractor shall give all necessary notice, obtain all permits, and pay fees required for the completion of his portion of the work. He shall also comply with all city, county and state laws and ordinances or regulations relating to portions of work which he is to perform.
14. All erosion control measures shall remain in place until site is stabilized & construction is complete.
15. Contractor to provide an area for concrete wash down and equipment fueling in accordance with Metro CP-10 and CP-13, respectively. Contractor to coordinate exact location with NPDES department during the pre-construction meeting. Grading permits to include temp's designed to control site wastes such as discarded building materials, chemicals, litter and sanitary wastes that may cause adverse impacts to water quality. The location of and/or notes referring to said temp's shall be shown on the EPSC plan.
16. The buffer along waterways will be an area where the surface is left in a natural state, and is not disturbed by construction activity. This is in accordance with the Stormwater Management Manual Volume 1 - Regulations.

Public Works Notes

1. All work within the public right of way requires an excavation permit from the department of public works.
2. Proof-rolling of all street subgrades is required in the presence of the public works inspector. Inspection of the binder course is required prior to final paving in the presence of the public works inspector. These requests are to be made 24 hours in advance.
3. Stop signs are to be 30 inch by 30 inch.
4. Street signs to have six inch white letters on a nine inch green aluminum blade, high intensity reflective.
5. All pavement marking are to be thermoplastic.

Landscape Notes

1. The landscape contractor shall coordinate all construction with the appropriate utility company and shall be responsible for and damage to utilities. The landscape contractor shall verify the exact location of all utilities and take precautions to prevent damage to the utilities.
2. All planting and mulch beds shall be sprayed with round-up (contractor's option) prior to the installation of mulch.
3. Plant materials and stumps indicated for removal shall be removed and disposed off-site by the contractor. Backfill holes with topsoil free of roots and rocks.
4. The landscape contractor shall be responsible for the fine grading of all planting areas.
5. All planting areas shall be fertilized with 12#/1000 s.f. of 10-10-10 fertilizer.
6. All planting beds shall have a minimum of 3" depth of shredded hardwood bark mulch.
7. The landscape contractor shall verify all material quantities. In the event of a discrepancy, the quantities shown on the plan will take precedence.
8. The landscape contractor shall provide the owner with written instructions on the proper care of all specified plant materials prior to final payment.
9. Existing trees to remain shall be protected from construction damage. Selectively prune dead wood.
10. All disturbed areas shall be planted with turf as indicated on the materials schedule.
11. All deciduous trees, existing and proposed shall be pruned to provide 4" minimum clear trunk unless otherwise noted.
12. The landscape contractor shall provide a one year warranty on all plant materials and replace any dead or dying material within that time period.
13. No plant materials should be substituted without authorization by Dale & Associates. Plant sizes shown are minimums required by the local municipality and materials shown have been selected specifically for this project.
14. All wire baskets shall be completely removed and disposed of, burlap should be removed or punctured in at least 5 places. Remove all twine from burlapped materials.
15. Guying is not allowed unless required by municipality or site conditions. The landscape contractor shall remove wires after a one year period.
16. No canopy tree shall be located within 15' of an overhead utility. No tree shall be located within a public utility easement. Locating plant materials within a drainage easement is acceptable, but only if installed as not to disturb existing drainage flow. In such instances, the materials shall be located no closer than 5' from the centerline of drainage.
17. Lighting plan to be coordinated with proposed planting plan. No light poles to be located in tree islands. See lighting plan for proposed light locations.

Water and Sewer Notes

1. All water and sewer construction shall be in accordance with specifications and standard details of the Metro Water Services.
2. The contractor is responsible for reimbursing the Metro water services the cost of inspection.
3. The contractor is to provide and maintain the construction identification sign for private development approved.
4. All connections to existing manholes shall be by coring and resilient connector method.
5. Reduced pressure backflow prevention devices (rpbp) or dual check valve will be required on all test and fill lines (jumper) needed for water main construction and must be approved by the Metro water services.
6. All water meters shall be a minimum of 24" not to exceed a maximum of 28" below finished grade.
7. Pressure regulating devices will be required on the customer side of the meter when pressures exceed 100 psi.
8. Pressure regulating devices will be required on the street side of the meter when pressures exceed 150 psi.
9. After completion of the sanitary sewer, the developer is responsible for the televising of the lines prior to final acceptance. The televising must be coordinated with the Metro Water Services inspection section. All costs will be borne by the developer.
10. Upon completion of construction of water and/or sewer, the engineer shall provide the Metro Water Services department with a complete set of as-built plans on most erasable mylars in reverse and in digital (.dwg) format. Sewer plans shall be sealed by a licensed professional engineer or a registered land surveyor and shall include actual field angles between lines, all actual service lines and tee locations, the distance of the end of the service line to property corners and lines and/or station and offset from sewer centerline to end of service line, the depth to the top of the end of the service line, and shall reflect all alignment and grade changes. Water line plans shall be sealed by a licensed professional engineer or a registered land surveyor and shall include offset distance from roadway centerline, or property line right of way, line depth, locations of hydrants, valves, reducers, tees and pressure reducing devices where applicable, all drawings must be completed and submitted prior to the sewers or water mains into the public system and any connections being made.
11. All water mains must be located within the paved area including all blow-off assemblies.

Architectural Notes

Building elevations for all street facades shall be provided with the final site plan. The following standards shall be met:

- A. Building facades fronting a street and courtyard shall provide a minimum of one principal entrance (doorway) and a minimum of 25% glazing.
- B. Windows shall be vertically oriented at a ratio of 1.5:1 or greater.
- C. EIFS and vinyl siding shall be prohibited.
- D. Finished ground floors and porches on units 1-9 shall be elevated a minimum of 18" to a maximum of 30" from the abutting average ground elevation. Units 10-11 shall be elevated a minimum of 12" to a maximum of 30".
- E. Porches shall provide a minimum of six feet of depth.


Standard SP Notes

1. The purpose of this SP is to receive preliminary approval to permit the development of a 11 unit multi-family (single family detached) residential development as shown.
2. Any excavation, fill or disturbance of the existing ground elevation must be done in accordance with Storm Water Management Ordinance No. 78-840 & Approved by the Metropolitan Department of Water Services.
3. This property does not lie within a flood hazard area as identified by FEMA ON MAP 47037C0236F. Dated: April 20, 2001.
4. All public sidewalks are to be constructed in conformance with Metro public works sidewalk design standards.
5. Wheel chair accessible curb ramps, complying with applicable Metro public works standards, shall be constructed at street crossings.
6. The required fire flow shall be determined by the Metropolitan Fire Marshal's office, prior to the issuance of a building permit.
7. Size driveway culverts per the design criteria set forth by the Metro Stormwater Manual (minimum driveway culvert in Metro right of way is 15' CMP).
8. Metro Water Services shall be provided sufficient & unencumbered ingress & egress at all times in order to maintain, repair, replace & inspect any stormwater facilities within the property.
9. Individual water and/or sanitary sewer service lines are required for each unit.
10. Solid waste pickup to be provided by roll-away containers for each unit.
11. The development of this project shall comply with the requirements of the Adopted Tree Ordinance 2005-328 (Metro Code Chapter 17.24, Article II, Tree Protection and Replacement, and Chapter 17.40, Article X, Tree Protection and Replacement Procedures).
12. Minor modifications to the preliminary SP plan may be approved by the Planning Commission or its designee based upon final architectural, engineering or site design and actual site conditions. All modifications shall be consistent with the principles and further the objectives of the approved plan. Modifications shall not be permitted, except through an ordinance approved by Metro Council that increase the permitted density or floor area, add uses not otherwise permitted, eliminate specific conditions or requirements contained in the plan as adopted through this enacting ordinance, or add vehicular access points not currently present or approved.
13. For any development standards, regulations and requirements not specifically shown on the SP plan and/or included as a condition of commission or council approval, the property shall be subject to the standards, regulations and requirements of the RMs-A zoning district as of the date of the applicable request or application.
14. Ownership for units may be divided by a horizontal property regime or a subdivision with a minimum lot size of 1,000 square feet.
15. The Final Site Plan shall depict a minimum 5 foot clear path of travel for pedestrian ways, including public sidewalks, and the location of all existing and proposed obstructions. Prior to the issuance of use and occupancy permits, existing obstructions within the path of travel shall be relocated to provide a minimum of 5 feet of clear access.
16. Principal Entrances for Units 3-9 shall be from the courtyard.


General Plan Consistency Note

The Specific Plan District proposed herein is located within Subarea #10, the Green Hills Community Plan. The specified land use policy for this site is a Transect 3 (T3) Neighborhood Maintenance policy (or T3 NM). The primary goal of the T3 NM policy is to preserve the general character of suburban neighborhoods as characterized by development pattern, building form, land use, and associated public realm.

As proposed, this Specific Plan District will maintain a streetscape along Hobbs Road while creating a sense of place within its interior. The plan as proposed will further the goals of the T3 NM policy by providing for future connectivity as shown on the attached plans. The connectivity proposed, both vehicular and pedestrian will result in a fluent development while still preserving over 40% of the natural terrain in its current state.



Development Summary	
Property Information	2202 Hobbs Road Road (Map 131-01, Parcel C2.24) & (Map 131-02, Parcel (19.20)) Nashville, Tennessee 37076 2.25 Total Acres
Council District	34 (Angie Henderson)
Owner of Record	Hauray & Smith Contractors 7065 Moores Lane Suite 300 Brentwood, TN 37027 Email: wmmorison@hauraysmith.com (615) 383 9070
Developer	Hauray & Smith Contractors 7065 Moores Lane Suite 300 Brentwood, TN 37027 Email: wmmorison@hauraysmith.com
Civil Engineer	Dale and Associates 616 Heather Place Nashville, Tennessee 37204 Contact: Adam Seeger, PE Phone: 615-297-5166 Email: adam@daleandassociates.net



Single family homes that do not exceed 3600 sq. ft. a minimum of 1000 @ 20 per shall be met. Final hydrant flow shall be provided during Final SP.


PRELIMINARY SPECIFIC PLAN DEVELOPMENT SUMMARY	
Use	Multi-Family (Detached Single Family Units)
Project Area	2.25 Acres (sq. ft.)
Property zoning - SP	Surrounding Zoning: RM20, RM4
Minimum lot size	Not Applicable
Number of Residential Units/Density	11 total dwelling units / units per acre
FAR	0.30 max / 0.25 proposed
ISR	0.50 max / 0.45 proposed
Street Setbacks	20' measured from E.O.W.
Side yard	Shoos may encroach up to 6'
Rear yard	5' min. Perimeter (6' Spacing between units)
Height standards	20' from Property line (North) 3 stories or 35' (measured from final grade to eave) max.
Parking and Access	
Ramp Location and Number	(1) - Hobbs Rd.
Distance to nearest existing ramp (Min. 30')	(Hobbs Rd.) (Private Drive) Exceeds 30' to West end South
Distance to Intersection	(Hobbs Road) = 1000' To East (Hillsboro Pike)
Required Parking	22 stalls required (2 stalls / unit)
Provided Parking	29 stalls provided

Sheet Schedule

- 1 C0.0 Notes and Project Standards
- 2 C1.0 Existing Conditions & Layout Plans

Drawing Date:
March 1, 2016
Revisions:
3/16/16 Per Planning
Comments


Preliminary SP
2202 Hobbs Road
Being Parcels 22 & 24 on Tax Map 131-01 &
Being Parcels 19 & 20 on Tax Map 131-02
Davidson County, Tennessee




PERMITS:

Dale & Associates
Civil/Structural/Environmental
Land Planning & Zoning
516 Heather Place
Nashville, Tennessee 37204
SP# 2015SP-110-001
D&A Project #15282
2202 Hobbs Rd
C0.0
Sheet 1 of 2


Notes & Project Standards



Existing Conditions



Layout, Utility, and Landscape Plan



Development Summary

Property Information
 2202 Hobbs Road
 (Map 131-01, Parcel 22.24) &
 (Map 131-02, Parcel 19.20)
 Nashville, Tennessee 37076
 2.25 Total Acres
 Council District 34 (Angie Henderson)

Owner of Record
 Haury & Smith Contractors
 7065 Moores Lane Suite 300
 Brentwood, TN 37027
 Email: wmonison@haury-smith.com
 (615) 383 9070

Developer
 Haury & Smith Contractors
 7065 Moores Lane Suite 300
 Brentwood, TN 37027
 Email: wmonison@haury-smith.com

Civil Engineer
 Dale and Associates
 516 Heather Place
 Nashville, Tennessee 37204
 Contact: Adam Seger, PE
 Phone: 615-297-5166
 Email: adam@daleandassociates.net

Pre / Post Calculations


Pre-development	
Total site area	= 2.25 acres
Pre-developed Wooded 'C'	= 1.25 ac @ 73
Pre-developed Turf 'C'	= 0.75 ac @ 79
Pre-developed Impervious	= 0.25 ac @ 98
Composite CN	= 78 CN
Post-development	
Total site area	= 2.25 acres
Post-developed Impervious	= 1.09 ac @ 98
Post-developed Turf 'C'	= 1.16 ac @ 79
Composite CN	= 88 CN

Preliminary calculations above shows that this project will increase the amount of runoff generated by this site. On-site mitigation shall be provided through the proposed rain gardens to ensure no adverse impacts & all water quantity requirements are met.

Drawing Date:
March 1, 2016

Revisions:
3/16/2016 Per
Planning Comments

Preliminary SP
2202 Hobbs Road
 Being Parcels 22 & 24 on Tax Map 131-01 &
 Being Parcels 19 & 20 on Tax Map 131-02
 Davidson County, Tennessee



PERMITS:

Stormwater Notes

- The soil types for this site is M&D which is a "C" hydrological soil groups.
- This site is responsible for water quality and water quantity.
- To provide the full water quality treatment of 80% TSS a water quantity/quality BMPs are proposed. Design of these features will be provided during the final SP process.
- Storm sewer system on this plan is shown schematically. Final design will be provided during the final SP process and will meet the requirements of the Stormwater management manual.
- This project will disturb more than 1 acre, therefore, a NOI will be submitted to TDEC during final SP process.
- This drawing is for illustration purposes to indicate the basic premise of the development. The final lot count and details of the plan shall be governed by the appropriate regulations at the time of final application.

Stormwater Calculations

Preliminary stormwater calculations have been completed for the area of proposed development (2.25 ac). Calculations show that the pre-development 100-yr flows for the area of proposed development are approximately 14,200 CFS. Post development flows for the 2.25 acres proposed for development have been calculated to be 14,200 CFS (based upon the composite curve numbers outlined on this sheet). Preliminary calculations indicate that two rain gardens provide all detention for this project to meet quantity requirements.

Water quality shall be also be provided through the storage within the two rain gardens shown herein. The site will be separated several smaller basins for each rain garden. Approximately 5,131 cf of water quality storage will be required for this project, and more detail will be provided during the final SP process.

Tree Density Notes

Metro tree density requirements will be addressed in final construction documents. At the preliminary phase of this project no detailed tree information is available. The majority of this property today is wooded, and a portion of this will remain. Sampling of remaining vegetation will be completed during final SP process to meet tree density.


Preliminary tree density calculations:

TDU's Req. = 2.25 ac x 0.60 ac x 14 = 23.16 TDU's Req
 24 proposed 2" caliper trees = 12 TDU's Pro

Remaining TDU's consists of existing vegetation to remain within the 0.50 Acres of open space as well as the preliminary buffer yards.

Irrigation Notes

Irrigation will be provided in more detail on final plan. Irrigation to be design/build by landscape contractor.



SP# 2015SP-110-001

D&A Project #15282

2202 Hobbs Rd

C1.0

Sheet 2 of 2